

Given Name
Student Number
Centre
Sionature

TWERS!

# SPECIAL EXAMINATION

All copies of the examination paper are to be returned to the examination supervisor

8 April 2009 WITH

6077AC Electrical Systems Safety - Capstone Assessment

Time allowed - Three hours plus Ten minutes reading time

25 Pages in this Question Booklet

#### TOTAL MARKS AVAILABLE =100

### Aids to be supplied by college:

None.

### Aids to be supplied by student:

- Australian/New Zealand Wiring Rules AS/NZS 3000:2007.
- Australian/New Zealand Standard Electrical Installations Selection of Cables AS/NZS 3008:1.1:1998.
- NSW Service and Installation Rules.
- Students own marginal notes, indexing and formal amendments may be included in the above regulation books.
- Pen, pencil, eraser, rule, calculator.

Section	Marks Possible	Marks Achieved
A	15	
В	20	
С	28	
D	37	
TOTAL	100	

#### Instructions to students:

- Mobile phones are to be turned off and removed from your person. You cannot access a mobile phone during this examination.
- All questions are to be attempted.
- All questions are to be answered in the space provided in this Question Booklet. Answers to Section A (multiple choice questions) are to be recorded on the Answer Sheet attached to this Question Booklet (Page 23).
- You are not to use any other reference books in this examination.
- The whole of this paper is to be handed to the supervisor upon completion.
- Equation Sheets are on Pages 24 and 25.

#### Aids permitted where indicated:

Standard	Bilingual	Technical	Programmable	Non-programmable	Electronic
Dictionaries	Dictionaries	Dictionaries	Calculators	Calculators	Devices
No	No	No	No	Yes	No

### SECTION A – (Cont'd)

### QUESTION 5. (1 Mark)

What is the minimum clearance for insulated aerial conductors above a porch awning?

- (a) 2 m
- (b) 0.5 m
- (c) 1 m
- (d) not permitted

### QUESTION 6. (1Mark)

What are the requirements for installing insulated unsheathed cables in trunking systems?

- (a) Cables shall be effectively retained in position and, where installed in a readily accessible position, shall not be removed without the use of tools
- (b) Covers shall be effectively retained in position and, where installed in a readily accessible position, shall not be removed without the use of tools
- (c) Trunking may only be used to enclose unsheathed cables in areas not readily accessible
- (d) Unsheathed cables are not permitted to be installed in cable trunking

#### QUESTION 7. (1Mark)

What would be an acceptable level of insulation resistance for a 230 V lighting circuit?

- (a) 50 ohms
- (b) 500 ohms
- (c) 50 M ohms
- (d) 500 k ohms

#### QUESTION 8. (1Mark)

Where a common neutral is used to supply a multiphase circuit for an oven hotplate combination, the size of the neutral must:

- (a) have a current carrying capacity equal to the sum of the protective devices supplying each circuit
- (b) have a current carrying capacity equal to the current carrying capacity of the smallest associated active conductor
- (c) have a current carrying capacity equal to the current carrying capacity of the largest associated active conductor
- (d) be at least 4 mm<sup>2</sup>

### SECTION A - (Cont'd)

### QUESTION 13. (1Mark)

A certificate of Compliance must be finalised when an electrical installation is tested and should be certified by:

- (a) the customer
- (b) the installing tradesperson
- (c) the electrician who completed the test
- (d) the electrical contractor

#### QUESTION 14. (1Mark)

The minimum disconnection time for protection against indirect contact for a fixed cooktop is:

- (a) unspecified
- (b) 0.4 sec
- (c) 400 ms
- (d) 5 sec

### QUESTION 15. (1Mark)

A circuit breaker installed to protect a circuit from overcurrent must operate when:

- (a) before the circuit current exceeds 1.45 the circuit breaker rating
- (b) before the circuit current exceeds the circuit breaker rating
- (c) before the circuit conductors exceed 40 °C
- (d) before the circuit conductors exceed 100 °C

## SECTION B – (Cont'd)


## QUESTION 4. (2 Marks)

What are the requirements for switching devices operating in a circuit fed from an isolated inverter?
AS/NZS 3000/2007 Reference (Clause number)
QUESTION 5. (2 Marks)
What are the requirements for soldered earth connections?
AS/NZS 3000/2007 Reference (Clause number)
2397125 3000/2007 Roler Gree (Clause Humber)
QUESTION 6. (2 Marks)
Identify an acceptable method for determining the maximum demand of a domestic circuit supplying an oven/grill and cook top.
······································
AS/NZS 3000/2007 Reference (Clause number)
QUESTION 7. (2 Marks)
Is it permissible to replace a single socket-outlet with a multiple socket-outlet when the existing circuit is not RCD protected, without upgrading the circuit to be RCD protected?
~
AS/NZS 3000/2007 Reference (Clause number)

### SECTION C – (28 Marks)

INSTRUCTIONS: This section involves calculations. Show all workings in the space provided. Marks will be awarded accordingly. Answers are to be highlighted or underlined.

QUESTION 1. (4 Marks)



# SECTION C - (Cont'd)

## QUESTION 2. (3 Marks)


An irrigation pump is supplied by 3 phase supply installed 500 mm underground over a distance of 45 m. The circuit comprises of 3 x 4 mm <sup>2</sup> V90 TPI cables run with a 2.5 mm <sup>2</sup> earth cable and the circuit is protected by a 25 A type D circuit breaker. Determine whether this installation satisfies the requirements for fault loop impedance ensuring the protective device will operate properly.
QUESTION 3. (3 Marks)
A single phase circuit supplying a domestic single socket outlet for a pool pump is supplied by a 20 A type combination RCD using a V75 TPS cable installed in HDPVC conduit 40 m from the main switchboard. The supply voltage is 230 V and the voltage drop in the consumers mains is negligible. Calculate the minimum size cable that may be used for the circuit based on voltage drop.
QUESTION 4. (3 Marks)
In a school workshop, determine the maximum distance a single phase 15 A socket outlet for the supply to a single phase welder can be installed from the distribution board given that the circuit will be using 4 mm <sup>2</sup> TPS cable installed partially surrounded by thermal insulation. The maximum volt drop allowed for the circuit is 4.9 V and the circuit is protected by a 20 A type D circuit breaker.

### SECTION C – (Cont'd)


### QUESTION 7. (6 Marks)

For the following installations, select the minimum permissible cable sizes for correct current carrying capacity, giving the appropriate references;

2 (a) A 3 phase final sub circuit to a lathe drawing 33 A per phase is installed in metallic conduit clipped to a wall. The cable type used is X90 TPI copper cable.



2 (b) A 4 core and earth, X-90, multicore copper, 3 phase submain is installed buried direct in the ground complying with category B requirements. The demand on the cable is 68 A per phase.



2 (c) A twisted 4 core PVC insulated aerial cable drawing 73 A, is installed in an area where the wind speed is 2 m/s.

	Main Dwelling	PVC Twis 4 core cal		
			Boat Shed	
Cabl	e size:	Reference:		


### SECTION D – (37 Marks)

INSTRUCTIONS: Answer all the following questions in the spaces provided. Some questions require drawing which must be neat and legible. Try to avoid lines crossing almost parallel when completing wiring diagrams to avoid any confusion as to which line exits the intersection.

### QUESTION 1. (4 Marks)

The equipment shown below is for a distribution board for a living unit. The four final subcircuits are to be connected using the breakers shown below.

Show on the diagram the necessary Active, Neutral and Earth connections to supply these circuits.



Light 2

Power 1

Power 2

Light 1

### SECTION D - (Cont'd)

### QUESTION 3. (4 Marks)


An insulation resistance test for a single phase low voltage power circuit is to be conducted.

- 2 (a) Draw and correctly label the appropriate circuit for this test to be carried out.
- 2 (b) State the position of the selector switch and the expected reading it would indicate.


Circle the correct answers.


Position:  $\Omega$ , 250 V, 500 V, 1000 V


Results: 50 k $\Omega$ , 100 K $\Omega$ , 500 k $\Omega$ , 5 M $\Omega$ 
















## SECTION D - (Cont'd)

### QUESTION 5. (4 Marks)

A polarity test is to be performed on a final sub-circuit containing light points. Record your results for the polarity test in the table below.



Switchboard connections



The results for correct polarity check would be:

Combination	Result		
Active-neutral	Ω		
Active-earth	Ω		
Neutral-earth	Ω		
Active-neutral Switched	Ω		
Active-earth Switched	Ω		
Neutral-earth switched	Ω		

### SECTION D - (Cont'd)

### QUESTION 7. (5 Marks)

Calculate the maximum demand of a sub-main supplying a town house with the following load:

- 53 lighting points
- 5 ceiling fans
- 2 exhaust fans
- 6 single socket outlets
- 16 double socket outlets
- 6.5 kW cook top
- 4.0 kW oven
- 5.0 kW ducted air conditioner (23 A)
- 3.6 kW quick recovery HWS
- 3.6 kW instantaneous HWS

Load Group	Load	No	Calculation	Demand Amperes
n				
			. •	
Camp → F		-		
<b>4</b> 31 > 1 ∞				* *
			N	
vec.				
		4,000		

Maximum demand:...

JF E	A R T A	WALES MENT ATION NING	100	
				MSN

ганиз маше
Given Name
Student Number
Centre
Signature

Answer Sheet - Section A (Multiple Choice Questions)

- 23 -

8 April 2009

# SPECIAL EXAMINATION

6077AC Electrical Systems Safety - Capstone Assessment

#### Instructions:

- Enter your personal details in the top right hand corner of this sheet.
- Place an 'X' in the box of your choice. If you make a mistake, circle your answer X and choose again.

Question	(a)	(b)	(c)	(d)
1				
2				
3				
4				
5				
6				
7				
8				
9				
10				
11				
12				
13				
14				
15				
Totals				
Total Correct So	ection	A		

Total Marks: Section A: ........../15

**END OF EXAMINATION** 

### SECTION B - (20 Mark)

INSTRUCTIONS: In this part of the assessment, you are required to answer a range of questions by using AS/NZS3000/2007. For each question, you are required to supply an answer to the question and the clause from AS/NZS3000/2007 that relates to your answer. One mark will be awarded for the correct answer and one mark for the correct clause number.

QUESTION 1. (2 Mark) What is the maximum disconnection time for a final sub-circuit supplying a socket outlet in a lounge room?
***************************************
AS/NZS 3000/2007 Reference (Clause number1.5.5.3.diA)
QUESTION 2. (2 Mark)
At what distance from the edge of a pool would a colour bond perimeter fence need to be bonded?
within arms reach 1.25m from waters edge
***************************************
AS/NZS 3000/2007 Reference (Clause number5.6,2.61.4.12)
QUESTION 3. (2 Mark) Where double insulation is maintained form the point of supply to the load terminals of the protective devices for the sub-mains and final sub-circuits, what will determine the minimum size of the main earth conductor?
In relation to the CSA of largest active conductor of the largest outgoing submain or final subcircuit.
AS/NZS 3000/2007 Reference (Clause number5.3.3.2.a)
QUESTION 4. (2 Mark) What are the requirements for switching devices operating in a circuit fed from an isolated inverter?
of a separated circuit
AS/NZS 3000/2007 Reference (Clause number7.4.4)
7 3 8 2 2

6077AB EY2008

Why are electrical installations divided into circuits?
Avoid danger and minimise inconvenience in the event of a fault
and facilite safe operation, inspection, testing and maintenance
AS/NZS 3000/2007 Reference (Clause number1.6.5)

6077AB EY2008

1

QUESTION 1 (Cont'd)

1 (a) Determine the phase impedance of the transformer.

$$S_{Fault} = S / Z\% = 500k/0.045 = ...$$

$$I = S_{Fault} / \sqrt{3}V = \frac{1}{3} \frac{1}$$

$$Z = V/I = 230/14.4 = 0.01440 \text{ Gr} + 4.4 \text{ mil}$$

1 (b) Assuming the transformer has a phase impedance of  $6m\Omega$ , determine the maximum 3 Ø prospective fault current at the POS (point A), AS3008.1has approximate tables to determine conductor resistance. Table 34 X90  $400mm^2$   $60m = 0.0039\Omega$ 

$$Z \text{ rotal} = 0.006 + 0.0039 = 0.0099 \Omega$$

$$I = V/Z = 230/0.0099 = 23.2kA$$

1 (c) Determine the system impedance, for a 3 Ø prospective fault current of 12kA at point 'C' the Sub Board

$$Z = V / I = 230 / 12kA = 0.0192\Omega$$

1 (d) If the Active Earth fault current is 4.8 kA at the SB (point C), determine the maximum earth fault current at the end of the final sub circuit assuming all fault current flows through the MEN at the MSB.

$$Zext = V/I = 230 / 4.8kA = 0.0 479\Omega$$

$$Z_{FSC} = Za + Ze = 0.196 + 0.315 = 0.511 \Omega$$

Ztotal 
$$+0.511 +0.0 479 = 0.5589 \Omega$$

If = 
$$V/Zt = 230 / 0.5589 = 411.5A$$

SECTION C - (Cont'd) OUESTION 5. (3 Marks)

> Three 3 phase circuits supplying similar loads are installed spaced on a single perforated cable tray. If the current drawn by each circuit is 35A per phase, determine




(a) The de-rating factor upplied to each cable and reference.

De-rating facture 1996......Reference:....T23 item 15

(b) The minimum current rating of the cables to supply the load.

QUESTION 6.

A 20A hot water circuit, a 20A cook top circuit and a 20A oven circuit are grouped together and clipped to the ceiling joist partially surrounded by bulk thermal insulation. Determine:




(a) The de-rating factor applied to each cable and reference.

(b) The minimum current rating of the cables to supply the load.

Current rating 28.6A  $\left(\frac{20}{0.1} = 28.6A\right)$ 

QUESTION 8. (3 Marks)

A three-phase, 400V sub-main has a route length of 42 meters and a maximum demand of 138A. The cables used are single core MIMS that are clipped to supports spaced from the wall be 20mm. The cable's temperature will not exceed  $90^{\circ}$ C.




### QUESTION 2 (4 marks)

A domestic installation is supplied with 16mm<sup>2</sup> double insulated consumers mains with 16mm<sup>2</sup> BW used for meter wiring.


- (a) Draw and correctly identify all cables used in the basic earthing system for the installation.(2marks)
- (b) Nominate the minimum size cables to be used. (2marks)

l6mm<sup>2</sup>




### QUESTION 4 (4marks)

A polarity test is to be performed on a final sub-ciruit containing socket outlets. Record your results for the polarity test in the table below. (3marks)



### Switchboard connections




Select correct meter position, circle correct selection,  $3\Omega$ ,  $500\Omega$ , 250V, 500V, 100V

The results for correct polarity check would be:

(3marks)

Combination	Result
Active-neutral	15Ω
Active- earth	5Ω
Neutral-earth	10Ω
Active-neutral Switched	$\Omega$
Active- earth Switched	$\Omega$
Neutral-earth switched	10Ω



### QUESTION 6 (7 marks)

Calculate the maximum demand of a 400V three phase sub-main to a factory having the following load:

- 15 x Mercury vapour high-bay lights rated at 4.5A each (3circuits)
- 90 x twin flucrescent light fittings 0.52A each (6circuits)
- 24 x double 10A single phase socket outlets (3circuits) =  $48 \times 10A = 6$
- 6 x three phase socket outlets 20A

• 3 x three phase socket outlets 15A

• 1 x 30kW three phase industrial air heater for factory heating

1 x three phase guillotine motor 20A

1 x three phase drill machine 15A

2 x three phase hydraulic presses 25A

1 x three phase air compressor 40A

	2 C. C. S	•	· <u> </u>	
1		ر د رد ت م		10
1	NA i	$L_{\rm ext} E_{\rm gas}$	11 3	13,6
	y P=	_/3	$V \perp \epsilon$	205 S
	01-1	_		•

See footnote e

				:	<u> </u>
Load	Load	Calculation	A phase	B phase	C phase
	type	7 05 20 050 20			
A	Light	5 x4.5+30 x 0.52 = 38.1 A five mercury vapour + thirty fives per phase	38.1	1.8c	38:1
Bii	10A	(1000W+100x15)/230= 10.87A	10.07	1000	100
7	SO	16 S/O per phose with permonal	10.87	10.87	10.87
Biii	20A	20+0.75(20x5+15x3)=128.75A	128.8	128.8	128.8
	SO				1240.0
C	Heater	30,000/1.73x400=43,3 A I = P/3V	43.3	43.3	43.3
D	Motors	40+0.75x25+0.5x(25+20+15) = 88.8A	පිලි•පි	8.88	88.88
<b>*</b>					
The same	X	Connected le par	in the	1.2. 40	
	,				
		Maximum	309.5	309:8 A	30g-8
		Demand	A	A	309.8 A

# QUESTIONS Smarks)

Fill in the certificate of compliance for question 8 as a new installation Installed and inspected by you.

CERTIFICATE OF COMPLIANCE -					Gustamer COPY		
ELECTRICAL WORK			CERTIF	GATE NO:			
CUST	omer detalls					And the second s	
Na.20	Part Y	man man to the second		-,	កក ជីជាប្រភព	The second secon	
Adules 3	<u>.</u>	<u></u>	1 1	-	ie luct	one mark for eac	
P.1035 5 1551		Pos	**************************************	r ikonsona		ct entry.	
	OAK DETAILS India	alə the type c	insialiakon and	l luppe - l sous pe	្រហារ ដល់ការ	ler ilns Natice	
Type of Installation	M Residential (	🛛 Gammer	al 🗆 indu	mer D 5	, F & 1	D Other	
Special Conditions	🗆 cvur 180 ames	🗆 High Ven	age 🔲 Haze Area	PCOUS DG	pechator	Uniterest Supply	
CERTIFICATE	MUST BE ISSUE	D TO THE	CUSTOMER	FOR ALL ELE	CTRICAL	. WORK	
,	ng type must ALSO b			_			
Mew Installation				☐ Metwork co		meterica	
1.1	erations to a switchbo	រងរជ ទា ខគ្គទទ្ធរ	aled equipment	Deleat Rec			
DETAILS OF EQU		····		'e iceo încreeșe o	the work a	rected by this Motice. Nach separate sheets	
EQUIPMENT	FATING	No.	PARTICULAR:		andernamenter en	englises a special save galacies as a fill of the common sense are sense as a fill of	
[] Switch paards					Medicumentum a	Marrie de la la description description de la propertie de la	
∐_Crouts			4			The state of the state of the state of	
(12) Agisting	114	60			્યું ક્	***************************************	
E Socket-cultets	132			35.	1 17.19	No. Therefore desirate and the second	
Esimatod increase	in total Alba	1>53+1	🖺 Increased In		- 1: 1:	11-11-11-11-11-11-11-11-11-11-11-11-11-	
Work is comilect		1.2.2.2.	******			lation/service mains inspection by DNSP	
The work has been b or supe	arried out : rvised by:				le.	The control of the co	
TEST REPORT	2 + ,p.o. at 2 -	Indicate th				arformed on the week. this separate skeets.	
🗹 Earthing system			इंडेविलेगी एमार्क्स र	leysse operation			
Zinsulation realst	ance MO	☑ v.	sual check that	instaliátion is sult	ible lor cen	reston to stoply	
☑ Felanty				rr sk <u>atom combije</u>			
Correct circuit o				nce (if hecessary			
Certificate complin	re carried out the at es with AS/NZS 300	oove tests ar O and is sulta	d visually checologically checologic	cked that the ins Aded use.	tallation wo	ork described in this	
Manto:	KEY		and the second	Licence No:			
Signature:	31/- 200	T.c.		Date of Testing:	:	) ) )	
(Name of DNSP or	ntractor give notice OFT), that the work	i bedinacoba		te has been com	pleted in a	cordance with the	
Mante:	mor Safety) Regulat	IION ZVVS		License No	الاي المرادي مماري	we will be a second of the sec	
	KEY	<del>- 1.</del>			<del>1</del>		
§ignalure:	IT I am to bear	<u> </u>		Date of Malice: Tolephone No.			
Adoless	والمستواد والمستود والمستواد والمستواد والمستود والمستواد والمستواد والمستود والمستواد والمستواد والمستود	y <u>w</u>		icapeans rig. er Öther Contact	, Na <del>laka Miki Nasana m</del> aya a		
	TRIBUTOR (DNSP)	REMARKS				erito de la compania	
Inspected 1			;	Date		· (Laborate 1)	
	**************************************				······································		
Comments:			production of the con-	بطريع المراجع الأربي المحج		neca	