


Topic Skills Practice 6.3

2.1.4 Use manufacturer's catalogues to select appropriate switchgear to sufficiently control and protect the PV power system, in accordance with AS/NZS 3000 and AS/NZS 5033 requirements. Indicate your selections below, using as many rows as necessary:

Control/Protection Device Selection				
#	Type of Device	Nominal Current	Nominal Voltage	Load-Break Capacity
1	Circuit breaker SAR-12240-6A PV switch 34A 32A at 400V	25A 32A at 400V	230V 212V 240V DC	☐ Yes ☐ No
2	Circuit breaker 15A 60	20A	230V 240V	☐ Yes ☐ No
3	PV Disconnect	32A	1000V	☐ Yes ☐ No
4				☐ Yes ☐ No
5				☐ Yes ☐ No


		Have your teacher/trainer check your answers	Teacher/Trainer Initials and Date	☒

Topic Skills Practice 6.3

2.1.5 Use manufacturer's catalogues to select a suitable d.c. wiring system to be installed between the array and the inverter(s). Indicate your selection below:

d.c. Wiring System Selection				
Installation Method:	Wiring enclosure solar			
Current Carrying Capacity				
Insulation Type	Minimum Current Carrying Capacity	Minimum Cable Size	AS/NZS 3008.1.1:2017	
			Table	Column
xlpe	38 A	4 mm	5	15
Voltage Drop				
Volts (V)	Percent (%)	Minimum Cable Size	AS/NZS 3008.1.1:2017	
			Table	Column
1.7 v	0.283 % 0.377 %	4 mm	34	6


$$vd = I \times L \times 2 \times Rc / 1000 \quad Vd\% = 1.7 / 600 \times 100$$

		Have your teacher/trainer check your answers	Teacher/Trainer Initials and Date	☒

Topic Skills Practice 6.3

2.1.6 Use manufacturer's catalogues to select a suitable a.c. wiring system to be installed between the inverter(s) and the connecting switchboard. Indicate your selection below:

a.c. Wiring System Selection				
Installation Method:	Wiring enclosure			
Current Carrying Capacity				
Insulation Type	Minimum Current Carrying Capacity	Minimum Cable Size	AS/NZS 3008.1.1:2017	
PVC	2.5 MM	23 A	Table 10	Column 11
Voltage Drop				
Volts (V)	Percent (%)	Minimum Cable Size	AS/NZS 3008.1.1:2017	
267 2.560V	1.13% 1.06%	2.5 MM	Table 42	Column 6

		Have your teacher/trainer check your answers Feedback	Teacher/Trainer Initials and Date	

RE001-RE0016-TSP06.3-R1

©Electrical Trades College
February 2023

Page 8 of 19

Topic Skills Practice 6.3

2.1.7 Using irradiation data for your current location, estimate the energy yield of the PV system, using the following equation:

$$E_{sys} = P_{array_STC} \times f_{man} \times f_{dirt} \times f_{temp} \times H_{tilt} \times n_{inv} \times n_{cables}$$

Include your working and answers in the following table. If unsure about estimating certain derating factors, ask your teacher/trainer for assistance.

PV System Derating		
Derating Factor	Determined From	Typical Value
Manufacturing tolerance	Manufacturer's data sheets	0.97
Dirt build up	Estimated based on site conditions	0.95
Operating temperature	Manufacturer's data sheets and site conditions	0.84
Efficiency of system cables	Estimated based on route length, resistivity etc.	0.97
Efficiency of the inverter	Manufacturer's data sheets	0.92

NOTE: $f_{temp} = 0.82$ yearly irradiation = 1570

Energy Yield Calculation	
Energy yield (E_{sys}) =	9549.96 5954435Wh
Rated output power of the array under STC (P_{array_STC}) =	4620 W 5280W
Manufacturing tolerance derating factor (f_{man}) =	0.97
Derating factor for dirt build up (f_{dirt}) =	0.95
Derating factor for temperature (f_{temp}) =	0.82 0.99
Total yearly irradiation for the site (H_{site}) =	2067 1576 kWh/m ²
Derating for the efficiency of the inverter (n_{inv}) =	0.98 catalogue
Derating for the efficiency of the system cables (n_{cables}) =	0.97

RE001-RE0016-TSP06.3-R1

©Electrical Trades College
February 2023

Page 9 of 19

Topic Skills Practice 6.3

Working:

Topic Skills Practice 6.3

1.8 Now use your estimated energy yield to determine the specific energy yield, using the following equation:

$$SY = \frac{E_{sys}}{P_{array_STC}}$$

Specific Energy Yield Calculation

Specific energy yield (SY) =	2067	1128	kWh/kW
Energy yield (E_{sys}) =	9549.96	5954435	Wh
Rated output power of the array under STC (P_{array_STC}) =	4620	5280	W

Working:



Feedback

Have your teacher/trainer check your answers

Teacher/Trainer Initials and Date



Feedback

Have your teacher/trainer check your answers

Teacher/Trainer Initials and Date



Topic Skills Practice 6.3

2.1.9 Calculate the performance ratio of the array using the following two equations;

$$PR = \frac{E_{sys}}{E_{ideal}}$$

$$E_{ideal} = P_{array_STC} \times H_{tilt}$$

Specific Energy Yield Calculation

Performance ratio	=	0.267	0.718	kWh/kWh
Actual energy yield (E_{sys})	=	9549.96	5954435	✓ kWh
Ideal energy yield (E_{ideal})	=	11014	8289600	✓ kWh

Working:

Topic Skills Practice 6.3



Have your teacher/trainer check your answers

Teacher/Trainer
Initials and Date



Feedback

Topic Skills Practice 6.3

3. Completing the Skills Practice

3.1 Skills Practice Review Questions

3.1.1 Complete this section after successfully completing Section 2.

1. List at least four factors that need to be considered when selecting and sizing PV system cable and switchgear.


Current carrying capacity / voltage drop / impedance / route length / installation method

2. What kinds of financial factors can impact the design of a PV power system?

Stc claims on energy production less power bills

3. What kinds of regulatory factors can impact the design of a PV power system?

Loss of accreditation id not installed to standards / grid supply impact

		Have your teacher/trainer check your answers	Teacher/Trainer Initials and Date	☒
Feedback				

UEE-EK135A-EK148A-TSP06.3-R1.1_WRU

©E-Oz Energy Skills Australia
September 2018

Page 19 of 19

SOLAR'S MOST TRUSTED



REC TWINPEAK 2 MONO SERIES

PREMIUM SOLAR PANELS WITH SUPERIOR PERFORMANCE

TwinPeak 2 Mono Series' solar panels feature innovative design with high panel efficiency, power output, enabling customers to get the most out of the space used for the installation.

Combined with industry-leading product quality and the reliability of a strong and established European brand, REC TwinPeak 2 Mono panels are ideal for residential and commercial rooftops worldwide.

Product not available in Germany.



MORE POWER
OUTPUT PER M²



IMPROVED PERFORMANCE
IN SHADED CONDITIONS



100%
PID FREE




REDUCES BALANCE OF
SYSTEM COSTS



ELIGIBLE FOR

REC TWINPEAK 2 MONO SERIES



Measurements in mm [in]

ELECTRICAL DATA @STC

	Product code*: RECxxxTP2M					
Nominal Power - P_{max} (Wp)	300	305	310	315	320	330
Wait Class Sorting (W)	-0/+5	-0/+5	-0/+5	-0/+5	-0/+5	-0/+5
Nominal Power Voltage - V_{mp} (V)	33.0	33.3	33.5	33.7	33.9	34.0
Nominal Power Current - I_{mp} (A)	9.11	9.17	9.26	9.36	9.45	9.56
Open Circuit Voltage - V_{oc} (V)	38.3	38.8	39.1	39.6	40.0	40.3
Short Circuit Current - I_{sc} (A)	10.01	10.04	10.07	10.10	10.13	10.19
Panel Efficiency (%)	18.0	18.3	18.6	18.9	19.2	19.5

Values at standard test conditions (STC: air mass AM1.5, irradiance 1000 W/m², temperature 25°C) based on a production spread with a tolerance of P_{max} , V_{mp} , I_{mp} , V_{oc} within one watt class. At a low irradiance of 200 W/m² at least 95% of the STC module efficiency will be achieved.
*Where xxx indicates the nominal power class (P_{max}) at STC indicated above.

ELECTRICAL DATA @NOMOT

	Product code*: RECxxxTP2M					
Nominal Power - P_{max} (Wp)	224	227	231	235	242	246
Nominal Power Voltage - V_{mp} (V)	30.7	31.0	31.2	31.4	31.6	31.7
Nominal Power Current - I_{mp} (A)	7.29	7.34	7.41	7.49	7.56	7.65
Open Circuit Voltage - V_{oc} (V)	35.6	36.1	36.4	36.8	37.2	37.5
Short Circuit Current - I_{sc} (A)	8.01	8.03	8.06	8.08	8.10	8.12

Nominal module operating temperature (NOMOT: air mass AM1.5, irradiance 800 W/m², temperature 20°C, windspeed 1 m/s).
*Where xxx indicates the nominal power class (P_{max}) at STC indicated above.

CERTIFICATIONS



REC 61215, REC 61730, REC 61730, REC 62804 (PSE)
REC 62716 (American Registration), REC 61710 (South Korea)
ISO 9001:2015, ISO 14001:2004, OHSAS 18001:2007

WARRANTY

	Standard	REC ProTrust
Installed by an REC Certified Solar Professional	No	Yes
System Size	Any	<25 KW 25-500 KW
Product Warranty (yrs)	20	25
Power Warranty (yrs)	25	25
Labor Warranty (yrs)	0	25
Power in Year 1	97.5%	97.5%
Annual Degradation	0.7%	0.7%
Power in Year 25	80.7%	80.7%

See warranty documents for details. Some conditions apply.

19.8% EFFICIENCY

20 YEAR PRODUCT WARRANTY
25 YEAR LINEAR POWER OUTPUT WARRANTY

GENERAL DATA

Cell type:	120 half-cut mono-Si p-type PERC
Glass:	6 strings of 20 cells, 3.2 mm solar glass, anti-reflection surface treatment
Backsheet:	Highly resistant polyolefin composite
Frame:	Anodized aluminum
Junction box:	3-part, 3 bypass diodes, IP65 in accordance with IEC 62485
Cable:	4 mm ² solar cable, 1.0 m in accordance with IEC 62485
Connectors:	5 pin MC4 PV-KBT4/PV-KST4 in accordance with IEC 62485, IP68 only when used in accordance with IEC 62485
Origin:	Made in Singapore

MAXIMUM RATINGS

Operational temperature:	-40 ~ +40 °C
Maximum system voltage:	1000 V
Design load (+) snow:	3600 Pa (367 kg/m ²)
Maximum test load (+):	5400 Pa (550 kg/m ²)
Design load (+) wind:	1600 Pa (163 kg/m ²)
Maximum test load (+):	2400 Pa (244 kg/m ²)
Max series fuse rating:	25 A
Max reverse current:	5 A

*Calculated using a safety factor
*See installation manual for mounting instructions

TEMPERATURE RATINGS*


Nominal Module Operating Temperature:	44.8 °C
Temperature coefficient of P_{max} :	-0.37 %/°C
Temperature coefficient of V_{oc} :	-0.28 %/°C
Temperature coefficient of I_{sc} :	0.04 %/°C

The temperature coefficients stated are linear values.

MECHANICAL DATA

Dimensions:	1675 x 997 x 38 mm
Area:	1.67 m ²
Weight:	18.5 kg

2019 TOP PERFORMER



2020 TOP PERFORMER



REC Group is an international pioneering solar energy company dedicated to empowering consumers with clean, affordable solar power in order to facilitate global energy transitions. Committed to quality and innovation, REC offers photovoltaic modules with leading high quality, backed by an exceptional low warranty claims rate of less than 10 GWh installed worldwide. REC employs 2,000 people and has an annual solar panel capacity of 1.8 GW. With over 10 GW installed worldwide, REC is empowering more than 16 million people with clean solar energy. REC Group is a Buester Elken company with headquarters in Norway, operational headquarters in Singapore, and regional bases in North America, Europe, and Asia-Pacific.



SG3K-D-NI/SG5K-D-NI

Residential Single Phase Inverter



HIGH YIELD

- Higher yield with Max. efficiency 98.4 %, European efficiency 98.0 %
- 12.5 A MPPT current, and compatible with bifacial modules
- Flexible PV string configurations, DC/AC ratio up to 1.4

SAFE AND RELIABLE

- Built-in surge arresters and residual current protection
- High anti-corrosion with aluminum alloy die casting


SMART MANAGEMENT

- Easy local and online monitoring via App or Web
- Export power control with smart energy meter


EASY AND USER FRIENDLY

- 11.5 kg compact design, plug and play installation
- Fast commissioning via LCD

CIRCUIT DIAGRAM



EFFICIENCY CURVE (SGSK-D-NI)



© 2022 Sungrow Power Supply Co. Ltd. All rights reserved. Subject to change without notice. Version 1.1

Type designation	503K-D-NI	505K-D-NI
Input (DC)		
Recommended max. PV input power	4000 W	6700 W
Max. PV input voltage	600 V	
Min. PV input voltage / Startup voltage	90 V / 120 V	
Rated input voltage	360 V	
MPP voltage range	90 V – 560 V	
MPP voltage range for rated power	160 V – 480 V	260 V – 480 V
No. of MPPTs	2	
Max. number of PV strings per MPPT	1	
Max. PV input current	25 A (12.5 A / 12.5 A)	
Max. PV short-circuit current	40 A (20 A / 20 A)	
Output Side Data		
AC output power	3000 VA	4999 VA
Rated AC output apparent power	3000 VA	4999 VA
Max. AC output current	13.7 A	21.7 A
Rated AC voltage	230 Vac	
AC voltage range	180 Vac – 276 Vac	
Rated grid frequency	50 Hz / 60 Hz	
Grid frequency range	45 Hz – 55 Hz / 55 Hz – 65 Hz	
Total harmonic distortion (THD)	< 3 % (of rated power)	
Power factor	> 0.99 / 0.8 leading – 0.8 lagging	
Feed-in phases / Connection phases	1 / 1	
Efficiency		
Max. efficiency	97.7 %	98.4 %
European efficiency		
Protection		98.0 %
PV reverse connection protection		Yes
AC short circuit protection		Yes
Leakage current protection		Yes
Grid monitoring		Yes
PV string current monitoring		Yes
DC switch		Yes
AFCL		No
24H loads monitoring		No
Overvoltage protection		No
General Data		AC Type II
Dimensions (W*H*D)		360*390*133 mm
Weight		11.5 kg
Isolation method		Transformerless
Ingress protection rating		IP65
Power loss in night mode		< 1W
Operating ambient temperature		-25 °C to 60 °C (+45 °C derating)
Allowable relative humidity		0 – 100 %
Cooling method		Natural cooling
Max. operating altitude		4000 m (= 2000 m derating)
Display / Communication		LCD / WLAN
PV connection type		MC4 (max. 6 mm ²)
AC connection type		Plug and play connector (max. 6 mm ²)
Certification		IEC62109-1, IEC62109-2, IEC62116, IEC61727, EN 61000-6-2, EN 61000-6-3, AS/NZS 4777.2:2020
Grid support		Active & reactive power control, power ramp rate control
Country of manufacture		China

Cluster Skills Test Task Sheet - Planning

Phase 1 – UEE30820

Learner Name:	ID:
College/ Campus:	Group/ Class:
Learner Signature:	Date:

Final Result of CST – Phase 1 (UEE30820) - Planning

The learner has demonstrated a satisfactory performance of identified steps listed.

Yes No

Assessor Name:	
Assessor Signature:	Date:

Comments:

Instruction:

The cluster test is broken down into three tasks – Task A to C. Planning for all tasks is initially undertaken to complete a job safety/hazard analysis, perform standard pre-work safety checks, development of wiring diagrams and material lists for each task. The carryout for each task can be carryout in any order and will be directed by your assessor. The carryout for each task involves the installation the circuit, testing of the circuit completing any necessary completion documentation.

- Time Allowed (to be specified by assessor):
- Orange shaded checkpoints are for assessor use only. Entering information in these areas may invalidate your assessment.
- Mobile phones and smart devices must be turned off and not accessed.
- Wait for the assessor to mark your work when requested.
- You will be allowed two (2) attempts at each check point to demonstrate the task described.
- If you are unsure about what you need to do, you should ask your assessor for guidance.
- Whilst carrying out skills activities you must follow all standard workplace procedures (i.e. Anti-discrimination, health and safety etc.) and ensure efficient / sustainable use of materials.

1. Planning the Cluster Skills Test

Your assessor will provide a pre-work briefing of the three tasks that you need to complete for this Cluster Skills Test.

1.1 Pre-Work Briefing

Your assessor will now brief you on tasks that you will be required to prepare for and undertake during this cluster skills test. Use the space provided below to note down a brief dot point description of the tasks.

Basic Description of Job:

Planning:

- Planning of Task A, B and C installations will require:
 - Completing a job safety/hazard analysis (risk assessment)
 - Conversion of the circuit diagram to wiring diagram for each of the three circuits.
 - Completion of material list for all three tasks.
- All work must be carryout that meets the AS/NZS 3000 Wiring Rules (current edition).
- All work must be carryout to meet sustainable and environmental requirements.
- Mandatory PPE before entering work shop **Hard hat, Hi vis, Safety boots**
- Task A, B and C can be undertaken in in any order, your RTO assessor will give you instructions concerning the order each task will be completed and the dimensions you will need to meet for each task.
- The following specifications for each task, provides the technical requirements, the physical layout of the circuit and the circuit diagram.

Task A:

- Lighting circuit using intermediate switching and an electric bell circuit operated by a pushbutton switch.
- Protected by an 8 A, 30 mA Type C RCBO.

1. Planning the Cluster Skills Test

- Wired in flat TPS cable fixed to a surface (plywood board) with suitable cable clips.

The circuit operates of 23 V a.c. 50 Hz.

Task B:

- Supply to a special outlet to enable a power pack to be plug in and supply a voltage divider/timing circuit to control a 12 V lamp.
- Protected by a 16 A, 30 mA Type C RCBO.
- Wired in TPI cable enclosed in rigid non-metallic conduit from the switchboard to special purpose outlet. Power pack connected via a flexible 3 core lead and 3 pin plug.
- The power supplies a 24 V d.c. to a voltage divider circuit.
- Suitable resistors to be selected to provide the following voltages:
 - 15 V d.c at P1 to ground
 - 12 V d.c at P2 to ground.
- The timing circuit needs to supply the lamp with 12 V d.c. after 5 seconds.
- Output of circuit supplies a single signal lamp wired in TPI enclosed in corrugated PVC conduit.

Task C:

- Supplies a control circuit consisting of a magnetic sensor, relay and solenoid and isolation device.
- Protected by a 20 A, 30 mA Type C RCBO.
- Wired from the switchboard to a metallic J-Box in circular TPS cable support on perforated cable tray. Wiring from the 4-way

1. Planning the Cluster Skills Test

metallic J-Box to a metal enclosure using TPI cable in metallic conduit.

- The isolation switch is an IP56 wired in TPI enclosed in flexible metallic conduit and magnetic sensor wired in flexible TPS cable enclosed in PVC duct fixed by double sided adhesive tape.

Job Safety/Hazard Analysis (PASS 36/36)

Complete a Job Safety/Hazard Analysis (JSA/JHA) for the work task described in the pre-work briefing, using the following procedure: 3 per Task step.

- Break the work task down into steps.
- Identify any hazards that may be encountered whilst performing each step.
- Classify and list the level of risk posed by each hazard (Levels 1 to 4)
- Select control measures to reduce the risk posed by each hazard.

Likelihood \ Severity	Likely	Possible	Unlikely
Death or permanent disability	1	1	2
Serious injury or chronic illness	1	2	3
Minor injury requiring first aid	2	3	4

1 = Extreme risk
2 = High risk
3 = Medium risk
4 = Low risk

Task Step	Hazard/s	Risk Level	Control Measure/s
Task A	Exposed live terminals	1	Isolation, AC voltage to be a rating of 23v
Task A	Sharp edge tools, and equipment	3	Safety gloves
Task A	Flying debris, dust	3	Safety glasses

1. Planning the Cluster Skills Test

Task B	Exposed live terminals	3	Isolation, dc v to be a rating of 15v max
Task B	Sharp edge tools, and equipment	3	Safety gloves
Task B	Flying debris, dust	3	Safety glasses
Task C	Sharp edge tools, and equipment	3	Safety gloves
Task C	Flying debris, dust	3	Safety glasses
Task C	Material and equipment on the floor	3-4	House keeping

- Based on your JSA/JHA, identify the tools and safety equipment needed to safely carry out the task. List of the required items in the table below.
- Obtain the required equipment from your assessor and check the condition of each item. Use the checklist to document your findings, and if any tools/equipment is unsafe indicate why in the comments column.

PASS (8/8)

Tools, Safety Equipment and PPE

Item	Condition		Comments
Safety gloves	☐ OK	☐ Unsafe	
Safety Glasses	☐ OK	☐ Unsafe	
Multimeter / IR Tester	☐ OK	☐ Unsafe	
Battery drills	☐ OK	☐ Unsafe	
Pliers	☐ OK	☐ Unsafe	
Screw Drivers	☐ OK	☐ Unsafe	
Conduit cutters	☐ OK	☐ Unsafe	
Miscellaneous (fixing etc.)	☐ OK	☐ Unsafe	
	☐ OK	☐ Unsafe	

1. Planning the Cluster Skills Test

3. Discuss your JSA/JHA and equipment list with your assessor, and then finalise your work preparation by completing the pre-work checklist.

Pre-Work Checklist

- ☐ JSA/JHA approved by assessor ☐ Required work permits obtained
- ☐ Control measures are in place ☐ Tools/equipment obtained and checked

I confirm I have read and understood the attached JSA/JHA, and agree to perform work in the manner detailed on it.

Name:

Signature:

Date:

4. The assessor must assess your work at this point. (Checkpoint 1)




Checkpoint 1 – Planning the Cluster Skills Test

Item	Description of Item	Satisfactory Yes/No	
		1 st	2 nd
	Pre-Work Briefing		
	Document Work Task		
1	Task Steps (Pass 9/9)		
2	Hazards (Pass 9/9)		
3	Risks (Pass 9/9)		
4	Control Measures (Pass 9/9)		
5	Equipment Selection (Pass 8/8)		
7	Equipment Safety Checks (Pass 8/8)		
8	Consultation and Approvals		
Assessor Initial:			

2. Task A Planning


1. Using the job specification – Task A, develop a wiring diagram in the space provided below. (PASS 7/7)



- Using the details in the specification and you're wiring diagram, develop a list of materials required to complete this task. Your list should give enough information about each material item so that your list would provide clear instructions to another person. This information may include ratings, sizes, type, colour, and catalogue numbers. Trade catalogues may be useful in helping select the material you need. Use the Material List Table to complete this item.

- The assessor must assess...

Item No.	
ETC001	100amp HRC fuses
ETC002	100amp HRC fuses
ETC003	80amp HRC fuses
ETC004	80amp HRC fuses
ETC005	1.5mm SDI cable
ETC006	2 core 1.5 TPS ca
ETC007	2 core & Earth 1
ETC008	2.5mm SDI cabl
ETC009	2 core 2.5mm
ETC010	2 core + Earth
ETC011	4 pole sub bo
ETC012	8 pole sub b
ETC013	12 pole sub
ETC014	Shallow m
ETC015	Deep mo



2. Using the details in the specification and your wiring diagram, develop a list of materials required to complete this task. Your list should give enough information about each material item so that your list would provide clear instructions to another person. This information may include ratings, sizes, type, colour, and catalogue numbers. Trade catalogues may be useful in helping select the material you need. Use the Material List Table to complete this item.

3. The assessor must assess your work at this point. (Checkpoint 2)

Checkpoint 2 – Task A Planning		
Item	Description of Item	Satisfactory Yes/No
1	Wiring Diagram (PASS 7/7)	1 st 2 nd
2	Material List	
Assessor Initial:		

Task A – Material List


Item No.	Item Description	Quantity
ETC001	100amp HRC fuses front wired	
ETC002	100amp HRC fuses back wired	
ETC003	80amp HRC fuses front wired	
ETC004	80amp HRC fuses back wired	
ETC005	1.5mm SDI cable	
ETC006	2 core 1.5 TPS cable	
ETC007	2 core & Earth 1.5mm TPS	
ETC008	2.5mm SDI cable	
ETC009	2 core 2.5mm TPS cable	
ETC010	2 core + Earth 2.5mm TPS	
ETC011	4 pole sub board	
ETC012	8 pole sub board	
ETC013	12 pole sub board	
ETC014	Shallow mounting blocks	
ETC015	Deep mounting blocks	
ETC016	Batten Holder	
ETC017	1-way shallow junction box	
ETC018	2-way shallow junction box	
ETC019	3-way shallow junction box	
ETC020	4-way shallow junction box	
ETC021	2 way right angled shallow junction box	
ETC022	1 gang 10 amp light switch	
ETC023	2 gang 10amp light switch	

Item No.	Item Description	Quantity
ETC024	10amp Intermediate switch mechanism	
ETC025	24v Doorbell switch	
ETC026	Single 10amp GPO	
ETC027	Double 10amp GPO	
ETC028	1.5mm cable clips	
ETC029	2.5mm cable clips	
ETC030	20mm rigid conduit	
ETC031	25mm rigid conduit	
ETC032	2 core + earth 1.5mm medium duty flexible cable	
ETC033	2 core + earth 1.5mm heavy duty flexible cable	
ETC034	Resistor	Values.....
ETC035	Capacitor	Values.....
ETC036	10amp 3 pin plug	
ETC037	15amp 3 pin plug	
ETC038	Power Pack/Bridge Rectifier	
ETC039	Wood screws	
ETC040	Hollow wall anchors	
ETC041	20mm conduit adapter	
ETC042	25mm conduit adapter	
ETC043	Plastic Enclosure	
ETC044	75mm cable tray	
ETC045	100mm cable tray	
ETC046	150mm cable tray	

Item No.	Item Description	Quantity
ETC047	225 cable tray	
ETC048	600mm cable tray	
ETC049	63amp 1 POLE MCB	
ETC050	20amp 1 POLE MCB	
ETC051	20amp 1 POLE MCB/RCD	
ETC052	16amp 1 POLE MCB/RCD	
ETC053	16mm PVC Duct	
ETC054	20mm PCV Duct	
ETC055	25mm PVC Duct	
ETC060	double sided tape	
ETC061	Metal enclosure	
ETC062	Magnetic sensor	
ETC063	300mm x 300mm switchboard surround	
ETC064	600mm x 600mm switchboard surround	
ETC065	2 core 16mm XLPE Cable	
ETC066	4 core 16mm XLPE Cable	
ETC067	20mm conduit	
ETC068	25mm conduit	
ETC069	32mm conduit	
ETC070	16 mm metal corrugated	
ETC071	20 mm metal corrugated	
ETC072	25 mm metal corrugated	
ETC073		

3. Task B Planning

- Using the job specification – Task B, develop a wiring diagram in the space provided below. **(PASS 9/9)**




- Using the details in the specification and your wiring diagram, develop a list of materials required to complete this task. Your list should give enough information about each material item so that your list would provide clear instructions to another person. This information may include ratings, sizes, type, colour, and catalogue numbers. Trade catalogues may be useful in helping select the material you need. Use the Material List Table to complete this item.
- The assessor must assess your work at this point. **(Checkpoint 3)**



Checkpoint 3 – Task B Planning

Item	Description of Item	Satisfactory Yes/No	
		1 st	2 nd
1	Wiring Diagram (PASS 9/9)		
2	Material List		
Assessor Initial:			

518 - CB.



- Using the details in the specification and your wiring diagram, develop a list of materials required to complete this task. Your list should give enough information about each material item so that your list would provide clear instructions to another person. This information may include ratings, sizes, type, colour, and catalogue numbers. Trade catalogues may be useful in helping select the material you need. Use the Material List

Task A – Material List

Item No.	Item Description	Quantity
ETC001	100amp HRC fuses front wired	
ETC002	100amp HRC fuses back wired	
ETC003	80amp HRC fuses front wired	
ETC004	80amp HRC fuses back wired	
ETC005	1.5mm SDI cable	
ETC006	2 core 1.5 TPS cable	
ETC007	2 core & Earth 1.5mm TPS	
ETC008	2.5mm SDI cable	
ETC009	2 core 2.5mm TPS cable	
ETC010	2 core + Earth 2.5mm TPS	
ETC011	4 pole sub board	
ETC012	8 pole sub board	
ETC013	12 pole sub board	
ETC014	Shallow mounting blocks	
ETC015	Deep mounting blocks	
ETC016	Batten Holder	
ETC017	1-way shallow junction box	
ETC018	2-way shallow junction box	
ETC019	3-way shallow junction box	
ETC020	4-way shallow junction box	
ETC021	2 way right angled shallow junction box	
ETC022	1 gang 10 amp light switch	
ETC023	2 gang 10amp light switch	


Item No.	Item Description	Quantity
ETC024	10amp Intermediate switch mechanism	
ETC025	24v Doorbell switch	
ETC026	Single 10amp GPO	
ETC027	Double 10amp GPO	
ETC028	1.5mm cable clips	
ETC029	2.5mm cable clips	
ETC030	20mm rigid conduit	
ETC031	25mm rigid conduit	
ETC032	2 core + earth 1.5mm medium duty flexible cable	
ETC033	2 core + earth 1.5mm heavy duty flexible cable	
ETC034	Resistor	Values.....
ETC035	Capacitor	Values.....
ETC036	10amp 3 pin plug	
ETC037	15amp 3 pin plug	
ETC038	Power Pack/Bridge Rectifier	
ETC039	Wood screws	
ETC040	Hollow wall anchors	
ETC041	20mm conduit adapter	
ETC042	25mm conduit adapter	
ETC043	Plastic Enclosure	
ETC044	75mm cable tray	
ETC045	100mm cable tray	
ETC046	150mm cable tray	

Item No.	Item Description	Quantity
ETC047	225 cable tray	
ETC048	600mm cable tray	
ETC049	63amp 1 POLE MCB	
ETC050	20amp 1 POLE MCB	
ETC051	20amp 1 POLE MCB/RCD	
ETC052	16amp 1 POLE MCB/RCD	
ETC053	16mm PVC Duct	
ETC054	20mm PCV Duct	
ETC055	25mm PVC Duct	
ETC060	double sided tape	
ETC061	Metal enclosure	
ETC062	Magnetic sensor	
ETC063	300mm x 300mm switchboard surround	
ETC064	600mm x 600mm switchboard surround	
ETC065	2 core 16mm XLPE Cable	
ETC066	4 core 16mm XLPE Cable	
ETC067	20mm conduit	
ETC068	25mm conduit	
ETC069	32mm conduit	
ETC070	16 mm metal corrugated	
ETC071	20 mm metal corrugated	
ETC072	25 mm metal corrugated	
ETC073		

4. Task C Planning

- Using the job specification – Task C, develop a wiring diagram in the space provided below. **(PASS 5/5)**

SB/LS




2. Using the details in the specification and your wiring diagram, develop a list of materials required to complete this task. Your list should give enough information about each material item so that your list would provide clear instructions to another person. This information may include ratings, sizes, type, colour, and catalogue numbers. Trade catalogues may be useful in helping select the material you need. Use the Material List Table to complete this item.

3. The assessor must assess your work at this point. (Checkpoint 4)

Checkpoint 4 – Task C Planning		Satisfactory Yes/No	
Item	Description of Item	1 st	2 nd
1	Wiring Diagram (PASS 5/5)		
2	Material List		
Assessor Initial:			

Task A – Material List

Item No.	Item Description	Quantity
ETC001	100amp HRC fuses front wired	
ETC002	100amp HRC fuses back wired	
ETC003	80amp HRC fuses front wired	
ETC004	80amp HRC fuses back wired	
ETC005	1.5mm SDI cable	
ETC006	2 core 1.5 TPS cable	
ETC007	2 core & Earth 1.5mm TPS	
ETC008	2.5mm SDI cable	
ETC009	2 core 2.5mm TPS cable	
ETC010	2 core + Earth 2.5mm TPS	
ETC011	4 pole sub board	
ETC012	8 pole sub board	
ETC013	12 pole sub board	
ETC014	Shallow mounting blocks	
ETC015	Deep mounting blocks	
ETC016	Batten Holder	
ETC017	1-way shallow junction box	
ETC018	2-way shallow junction box	
ETC019	3-way shallow junction box	
ETC020	4-way shallow junction box	
ETC021	2 way right angled shallow junction box	
ETC022	1 gang 10 amp light switch	
ETC023	2 gang 10amp light switch	



2. Using the details in the specification and you're wiring diagram, develop a list of materials required to complete this task. Your list should give enough information about each...

Item No.	Item Description	Quantity
ETC024	10amp Intermediate switch mechanism	
ETC025	24v Doorbell switch	
ETC026	Single 10amp GPO	
ETC027	Double 10amp GPO	
ETC028	1.5mm cable clips	
ETC029	2.5mm cable clips	
ETC030	20mm rigid conduit	
ETC031	25mm rigid conduit	
ETC032	2 core + earth 1.5mm medium duty flexible cable	
ETC033	2 core + earth 1.5mm heavy duty flexible cable	
ETC034	Resistor	Values.....
ETC035	Capacitor	Values.....
ETC036	10amp 3 pin plug	
ETC037	15amp 3 pin plug	
ETC038	Power Pack/Bridge Rectifier	
ETC039	Wood screws	
ETC040	Hollow wall anchors	
ETC041	20mm conduit adapter	
ETC042	25mm conduit adapter	
ETC043	Plastic Enclosure	
ETC044	75mm cable tray	
ETC045	100mm cable tray	
ETC046	150mm cable tray	

Item No.	Item Description	Quantity
ETC047	225 cable tray	
ETC048	600mm cable tray	
ETC049	63amp 1 POLE MCB	
ETC050	20amp 1 POLE MCB	
ETC051	20amp 1 POLE MCB/RCD	
ETC052	16amp 1 POLE MCB/RCD	
ETC053	16mm PVC Duct	
ETC054	20mm PCV Duct	
ETC055	25mm PVC Duct	
ETC060	double sided tape	
ETC061	Metal enclosure	
ETC062	Magnetic sensor	
ETC063	300mm x 300mm switchboard surround	
ETC064	600mm x 600mm switchboard surround	
ETC065	2 core 16mm XLPE Cable	
ETC066	4 core 16mm XLPE Cable	
ETC067	20mm conduit	
ETC068	25mm conduit	
ETC069	32mm conduit	
ETC070	16 mm metal corrugated	
ETC071	20 mm metal corrugated	
ETC072	25 mm metal corrugated	
ETC073		

EE000023	-	C020B
EE000027	-	E101A
EE000016	-	E137A
EE000019	-	E102A
EE000020	-	E105A
EE000051	-	E107A
EE00001	-	K142A

17200
 E090046
 E090044
 E090005
 4 — E1021
 — F102A

EEEL0021 } — E101
EEEL0019 }
EEEL0020 — G102A
EEEL0023 — G106A

WFFEL0008
WFFEL0009
WFFEL0010

9033

UTFL 0024 } — 0006
UTFL 0025 }

✓ 46662003 - 40631

466629547

✓UGFL0014 - (2103/104)

✓ HEEEL 9005 - 9109A

46-15 9007

✓ $u_{CELODIB} \sim 9107A$ $u_{gl. m. l.}$

✓ SUBFLO 12 ~ C 103/104

14LTA12009

UFTDRRF 06

UFGCL0039 - G105A

CPPSEC 2021/23/26

514 Nt

2526 m or 3a # # 7.

Wachau

7 m 252 ✓

2014902

$7(10)$
 $10 \rightarrow 7(6)$
 $12 \rightarrow 11$
 $13 \rightarrow 13$
 $15 \rightarrow 12$
 $40(71)$
 $42(62)$
 $46(84)$
 $48(90)$
 $50(92)$